Silver Plan

# Sl.no.	Project	Description	Rate	Amo
Section -A-Living				
1	**TV Bottom Unit & Ledg**	Providing and fixing of TV unit with 12mm plywood of paneling on the wall, they paneling will be finished by 1mm laminated, and bottom unit to be made of 19mm plywood with 6mm plywood backing, the bottom unit will be of drawer type and box type with laminate finish as required area only.	0 / Sqft	0
2	**Wall Paper**	Providing customised wall paper fixed on the wall as required area.	0 / Sqft	0
Section -B-Bed Room 1				
3	**Wardrobe**	Providing and fixing box Wardrobe Made of 19mm plywood and 6 mm ply wood backing 21'' depth and 84'' height .two drawers will be provided with lock .the shutter will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on inner side.	0 / Sqft	0
Section -C-Bed Room 2				
4	**Wardrobe**	Providing and fixing box Wardrobe Made of 19mm plywood and 6 mm ply wood backing 21'' depth and 84'' height .two drawers will be provided with lock .the shutter will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on inner side.	0 / Sqft	0
Section -D- Kitchen				
5	**Bottom Unit**	Providing and fixing of kitchen bottom box unit made of 19mm plywood 24'' depth and 33'' height fixed with 19mm plywood shutter with 1mm laminate side as per the outer side and 0.8mm on inner side as per the given design shutter to be fixed with hinges.	0 / Sqft	0.
6	**Wall Unit**	Providing and fixed of kitchen wall box unit made of 19 mm ply wood 13'' depth and 27'' height fixed with aluminium profile shutter with frosted glass 19mm plywood shutter with 1mm laminate on the outer side and 0.8mm on inner side as per the given design shutter to be fixed with hinges.	0 / Sqft	0.
7	**Loft**	Providing and fixing of frame type loft made of 19mm ply height to be selling the shutter will be of 19mm ply with 1 mm laminated on outside and 0.8mm inner side fixed with hinges.	0 / Sqft	0.
8	**Mics Amount**	service, labour, etc charges	0 / Sqft	0.

TOTAL Amount: 0.

Gold Plan

# Sl.no.	Project	Description	Rate	Amou
Section -A-Living				
1	**TV Unit Paneling & Bottom Storage**	Providing and fixing TV unit wall paneling , with made 12mm Plywood on top of louver finished as per the design.Bottom unit storage made of 19mm plywood and 6mm plywood backing, The shutters will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on the inner side fixed with hinges.	0 / Sqft	0.0
2	**Wall Paper**	Providing customised wall paper fixed on the wall as required area.	0 / Sqft	0.0
3	**False Ceiling**	Providing and fixing 12.5mm Thk. Gypsum board on metallic grid. The grid shall consist of the following components. Regular channel, hanger, Cleat. Finally, the 12.5 mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisites filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, and finally finished with 2 coats of emulsion paint.	0 / Sqft	0.0

Section -C- Bed Room 2				
5	**Wardrobe**	Providing and fixing box Wardrobe Made of 19mm plywood and 6 mm ply wood backing 21'' depth and 84'' height .two drawers will be provided with lock .the shutter will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on inner side.	0 / Sqft	
Section -D- Kitchen				
6	**Wall Unit**	Providing and fixed of kitchen wall box unit made of 19 mm ply wood 13'' depth and 27'' height fixed with aluminium profile shutter with frosted glass 19mm plywood shutter with 1mm laminate on the outer side and 0.8mm on inner side as per the given design shutter to be fixed with hinges.	0 / Sqft	
7	**Bottom Unit**	Providing and fixing of kitchen bottom box unit made of 19mm ply wood 24'' depth and 33'' height fixed with 19mm plywood shutters with 1mm laminate side as per the outer side and 0.8mm on inner side as per the given design shutter to be fixed with higes.	0 / Sqft	

TOTAL

Platinum Plan

# Sl.no.	Project	Description	Rate	An
Section -A-Living				
1	**Tv Unit Louvers With Paneling**	Providing and fixing of TV unit with 12mm plywood of louvers paneling on the wall, they paneling will be finished by 1mm laminated, and bottom unit to be made of 19mm plywood with 6mm plywood backing, the bottom unit will be of drawer type and box type with laminate finish as required area only.	0 / Sqft	
2	**False Ceiling**	Providing and fixing 12.5mm Thk. Gypsum board on metallic grid. The grid shall consist of the following components. Regular channel, hanger, Cleat. Finally, the 12.5 mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisites filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, and finally finished with 2 coats of emulsion paint.	0 / Sqft	
Section -B-Master Bed Room				
3	**Wardrobe**	Providing and fixing box wardrobe made of 19mm plywood and 6 mm ply wood backing 21'' depth and 84'' height .Two drawers will be provided with lock .The shutter will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on inner side.	0 / Sqft	
4	**TV Unit**	Providing and fixing of TV unit with 12mm plywood of paneling on the wall, they paneling will be finished by 1mm laminated, and bottom unit to be made of 19mm plywood with 6mm plywood backing, the bottom unit will be of drawer type and box type with laminate finish as required area only.	0 / Sqft	
5	**False Ceiling**	Providing and fixing 12.5mm Thk. Gypsum board on metallic grid. The grid shall consist of the following components. Regular channel, hanger, Cleat. Finally, the 12.5 mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisites filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, and finally finished with 2 coats of emulsion paint.	0 / Sqft	
Section -C- Son Bed Room				
6	**Wardrobe**	Providing and fixing box wardrobe made of 19mm plywood and 6 mm ply wood backing 21'' depth and 84'' height .Two drawers will be provided with lock .The shutter will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on inner side.	0 / Sqft	
7	**TV Unit**	Providing and fixing of TV unit with 12mm plywood of paneling on the wall, they paneling will be finished by 1mm laminated, and bottom unit to be made of 19mm plywood with 6mm plywood backing, the bottom unit will be of drawer type and box type with laminate finish as required area only.	0 / Sqft	

8	**False Ceiling**	Providing and fixing 12.5mm Thk. Gypsum board on metallic grid. The grid shall consist of the following components. Regular channel, hanger, Cleat. Finally, the 12.5 mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisites filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, and finally finished with 2 coats of emulsion paint.	0 / Sqft
Section -D- Guest Bed Room			
9	**Wardrobe**	Providing and fixing box wardrobe made of 19mm plywood and 6 mm ply wood backing 21'' depth and 84'' height .Two drawers will be provided with lock .The shutter will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on inner side.	0 / Sqft
10	**False Ceiling**	Providing and fixing 12.5mm Thk. Gypsum board on metallic grid. The grid shall consist of the following components. Regular channel, hanger, Cleat. Finally, the 12.5 mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisites filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, and finally finished with 2 coats of emulsion paint.	0 / Sqft
Section -E- Kitchen			
11	**Wall Unit**	Providing and fixed of kitchen wall box unit made of 19 mm ply wood 13'' depth and 27'' height fixed with aluminium profile shutter with frosted glass 19mm plywood shutter with 1mm laminate on the outer side and 0.8mm on inner side as per the given design shutter to be fixed with hinges.	0 / Sqft
12	**Bottom Unit**	Providing and fixing of kitchen bottom box unit made of 19mm ply wood 24'' depth and 33'' height fixed with 19mm plywood shutters with 1mm laminate side as per the outer side and 0.8mm on inner side as per the given design shutter to be fixed with higes.	0 / Sqft

Diamond Plan

# Sl.no.	Project	Description	Rate
Section -A-Living			
1	**TV Unit Marble With Louvers**	Providing and fixing of TV unit with 12mm plywood of marble and louver paneling on the wall, the paneling will be finished by 1mm laminated, and bottom unit to be made of 19mm plywood with 6mm plywood backing, the bottom unit will be of drawer type and box type with laminate finish as required area only.	0 / Sqft
2	**Glass False Ceiling**	Providing and fixing Glass ceiling, after completion of Gypsum ceiling under screwed 12mm Plywood then pasting the required 5mm Glass as per the design.	0 / Sqft
3	**Wall Paneling**	Providing and fixing wall paneling , with made 12mm Plywood base on top of and finished as per the design.	0 / Sqft
Section -B-Master Bed Room			
4	**Wardrobe with glass**	Providing and fixing box wardrobe made of 19mm plywood and 6 mm ply wood backing 21'' depth and 84'' height .two drawers will be provided with lock .the shutter will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on inner side.12mm Glass mirror as agreed design.	0 / Sqft

5	**TV Unit**	Providing and fixing of TV unit with 12mm plywood of paneling on the wall, they paneling will be finished by 1mm laminated, and bottom unit to be made of 19mm plywood with 6mm plywood backing, the bottom unit will be of drawer type and box type with laminate finish as required area only.	0 / Sqft
6	**False Ceiling**	Providing and fixing 12.5mm Thk. Gypsum board on metallic grid. The grid shall consist of the following components. Regular channel, hanger, Cleat. Finally, the 12.5 mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisites filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, and finally finished with 2 coats of emulsion paint	0 / Sqft
7	**Headboard Back wall Paneling**	Providing and fixing 12mm ply with 1 mm laminate finish with made 6mm Plywood base on top of cushion as per the design.	0 / Sqft
Section -C- Son Bed Room			
8	**Louver Wardrobe Door**	Providing and fixing box louver wardrobe door made of 19mm plywood and 6 mm ply wood backing 21 depth and 84 height .two drawers will be provided with lock .the shutter will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on inner side.	0 / Sqft
9	**False Ceiling**	Providing and fixing 12.5mm Thk. Gypsum board on metallic grid. The grid shall consist of the following components. Regular channel, hanger, Cleat. Finally, the 12.5 mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisites filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, and finally finished with 2 coats of emulsion paint	0 / Sqft
10	**TV Unit**	Providing and fixing of TV unit with 12mm plywood of paneling on the wall, they paneling will be finished by 1mm laminated, and bottom unit to be made of 19mm plywood with 6mm plywood backing, the bottom unit will be of drawer type and box type with laminate finish as required area only.	0 / Sqft
Section -D- Guest Bed Room			
11	**Wardrobe**	Providing and fixing box wardrobe made of 19mm plywood and 6 mm ply wood backing 21'' depth and 84'' height .two drawers will be provided with lock .the shutter will be of 19mm plywood with 1mm laminate on outer side and 0.8mm laminate on inner side.	0 / Sqft
12	**False Ceiling**	Providing and fixing 12.5mm Thk. Gypsum board on metallic grid. The grid shall consist of the following components. Regular channel, hanger, Cleat. Finally, the 12.5 mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisites filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, and finally finished with 2 coats of emulsion paint	0 / Sqft
Section -E- Kitchen			
13	**Bottom Unit**	Providing and fixing of kitchen bottom box unit made of 19mm plywood 24'' depth and 33'' height fixed with 19mm plywood shutter with 1mm laminate side as per the outer side and 0.8mm on inner side as per the given design shutter to be fixed with hinges.	0 / Sqft
14	**TALL UNIT**	PProviding and fixing of kitchen storage made of 19mm plywood and 6mm plywood backing, 0.8mm laminate on the inner side Outside surface will be 1 mm laminate finish, door will be fixed with hinges.	0 / Sqft